

5. The final acceptance of the tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Abstract estimate of quantities for the work of Permanent measures for the control of Malaria in Belur Town.

| Sl. No. | Description of work                                                                                                                                    | Unit    | Quantity | Rate      |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------|---------|----------|-----------|
|         | <i>I. Regrading the Bed of Fort Moat.</i>                                                                                                              |         |          | Rs. a. p. |
| 1       | Earthwork cutting the bed of the fort moat in high mounds                                                                                              | Cyd.    | 2,819    |           |
| 2       | Earth filling for the scours with a lead of 2 furlongs with the earth available from cutting high mounds                                               | "       | 2,819    |           |
| 3       | Earth filling the deep scours with fresh earth carted lead being 1 mile                                                                                | "       | 6,830    |           |
|         | <i>II. Constructing dry stone vent ways.</i>                                                                                                           |         |          |           |
| 1       | Earthwork cut opening the bund                                                                                                                         | "       | 722      |           |
| 2       | Providing dry stone revetment for the side walls with available old stones                                                                             | "       | 111      |           |
| 3       | Providing and fixing new covering slabs 6" thick over the vent including hammer dressing the edges, etc., complete                                     | S.ft. c | 600      |           |
| 4       | Providing earth cushion over the vent ways including watering and tamping                                                                              | C.yd.   | 412      |           |
|         | <i>III. Revetting the bed of the Fort moat with rough stone boulders with jelly wedging, etc., in steep slope for protecting from scouring action.</i> |         |          |           |
|         |                                                                                                                                                        | "       | 93       |           |
|         | <i>IV. Filling the scours in Kalasankere tank waste weir.</i>                                                                                          |         |          |           |
| 1       | Filling up the deep scours with rough stone boulders and pitching with jelly wedging, etc., complete                                                   | "       | 760      |           |
| 2       | Cement concrete groutings after filling up the boulders for scours for protecting from scouring action                                                 | S.yd.   | 71.06    |           |
| 3       | Constructing retaining walls with rough stone in mortar including earth work, etc., complete                                                           | C.ft.   | 450      |           |
| 4       | Cutting open a lead off channel in the centre with proper gradient and filling in pits including a lead of 100 feet                                    | C.yd.   | 256      |           |

K. S. HUTCHA RAO,  
Sanitary Engineer.

#### KOLAR DIVISION.

*Abstract Notification dated 6th November 1939:*

The attention of the public is invited to the detailed notification, dated 4th November 1939, published on pages 2251-2254 of Part VI of the *Mysore Gazette*, dated 9th November 1939, regarding tenders for restoration of Doddakondrahalli Melinakere Minor Tank, Register No. 467-444, Antamani Taluk.

The last date for receiving tenders is 1st December 1939, up to 2 P.M.

C. R. IYENGAR,  
Executive Engineer.